

GUIDE SPECIFICATIONS

**SECTION 07120
HOT POLYMERIC FLUID APPLIED WATERPROOFING
RAM-TOUGH 250 DM WITH PROTECTION COURSE**

PART 1 - GENERAL

1.00 GENERAL

The general conditions, special conditions, applicable portions of Division 1 and requirements for general construction and subtrades form part of this specification.

1.01 RELATED SECTIONS

- Section 02050 Demolition
- Section 03300 Concrete
- Section 04100 Masonry
- Section 06100 Carpentry
- Section 07600 Sheet Metal
- Section 07710 Roofing Accessories
- Section 07900 Caulking & Sealants

1.02 SCOPE

The Work includes supplying all materials, labor and equipment to complete the installation of the Hot Polymeric Fluid Applied Double Membrane Waterproofing System for the following areas:

roof and terrace decks, associated walls and elsewhere as shown.

1.03 QUALIFICATIONS

The Waterproofing System shall be installed only by an Applicator approved and licensed by the Manufacturer. Polymerized bitumen and reinforcing sheet shall be supplied by the same firm to insure single-source responsibility. Materials supplied for installation will be tested by an independent laboratory to guarantee compliance with published physical

properties.

The Manufacturer shall have a minimum of ten (10) years documented experience with the system specified herein.

1.04 SUBMITTALS

- A. Submit Manufacturer's written approval or license of applicator for installation of the herein specified Waterproofing System.
- B. Submit Manufacturer's sample Fifteen Year Labor and Material System Warranty and Manufacturer's Intent to Warranty Certification for this project.
- C. Submit most recent copy of Manufacturer's literature applicable to products and specifications to be used, as specified herein, including applicable flashing details.
- D. Submit three sheet samples, approximately 8 inches x 10 inches, of waterproofing membrane reinforcement, flashing material and protection course.
- E. Submit three samples, approximately 8 inches x 10 inches, of the insulation and drainage.
- F. Submit three samples of elastomeric bitumen.
- G. Submit evidence of Manufacturers history of production for the system specified herein. A minimum of ten (10) years experience is required. Documentation shall include job lists with project size, Architect of record, installing Applicator, telephone numbers and contact names.
- H. Submit, in duplicate, certification from the primary Manufacturer, properly attested by a corporate officer, stating that all materials being supplied comply with the specifications and requirements of the contract documents, including conformance with all federal, state and local building codes including United States Code Section 41:10, Subsections a-d, popularly known as the "Buy American Act".

1.05 QUALITY ASSURANCE

All the materials specified herein are cited as a minimum standard of quality and shall not preclude consideration of equal or superior materials. All suggested "equivalent materials" or other substitutions are to be submitted to the Architect for consideration a minimum of ten (10) days prior to the bid date. Submittal shall include all evidence of compliance or superiority of material from the proposed substitute Manufacturer. If accepted by the Architect, an addendum will be issued to all bidders for their consideration of the proposed

substitute Manufacturer. Determination of equivalency of all substitutions shall rest exclusively with the Architect and such decision shall be final.

1.06 DELIVERY, STORAGE AND HANDLING

- A. Deliver and store materials under provisions of General Conditions Section.
- B. Deliver materials to jobsite on pallets. Package labels shall indicate material name, production date and product code.
- C. Store materials in dry, protected areas in an upright position. Control temperature of storage areas in accordance with Manufacturer's instructions. Protect materials from moisture with breathable tarps on sides and top surfaces.

1.07 PROJECT CONDITIONS

- A. Follow local, state & federal regulations, safety standards and codes. When a conflict exists use the stricter requirement.
- B. Do not apply waterproofing materials unless proper bitumen application temperatures (approximately 350°F-400°F) can be maintained, or when moisture in any form (i.e. rain, dew, ice, frost, snow, etc.) is present on the deck. Do not heat bitumen above 400°F.
- C. Ensure deck is structurally sound to support the live and dead load requirements of the waterproofing system and sufficiently rigid to support construction traffic.
- D. Sequencing and Scheduling: The Work shall be scheduled in the construction sequence so that designated complete contiguous areas can be installed and completed, including overlay wear courses, before other construction trades are allowed in the area. Prior to starting the Work, all drains shall be operative and all deck projections, sleeves and all other penetrations shall be installed, in place and operative.

1.08 CODE COMPLIANCE

It shall be the Applicator's responsibility to ensure that all the Work done under this project shall be in compliance with applicable code requirements including obtaining any required permits prior to the start of the Work.

1.09 WARRANTY

Supplier of the Waterproofing System shall furnish its standard Fifteen Year Warranty for

labor and materials, including the membrane, membrane flashings, protection course, drainage medium and concrete pavers, where present.

PART 2 - PRODUCTS

2.01 ACCEPTABLE MANUFACTURERS

Products manufactured or accepted by the Barrett Company, or Architect approved equal.

2.02 MATERIALS

A. Waterproofing Membrane:

1. Hot Polymeric Waterproofing: **ram-Tough 250** SBS Kraton® modified bitumen shall have inert mineral stabilizer. Material shall comply with the following specifications:

<u>TEST</u>	<u>CGSB 37-GP-50M REQUIREMENTS</u>	<u>TYPICAL TEST RESULT</u>
Flash Point, °C	Min. 260	327
Penetration, 0.1 mm	Max. 110 @ 25°C Max. 200 @ 50°C	83 165
Flow, mm	Max. 3	0.5
Toughness, J	Min. 5.5	11.7
Ratio of Toughness, J/N to Peak Load	Min. 0.040	0.059
Adhesion	Min. 1	1
Water Vapor Permeance ng/Pa.s.m_	Max. 1.7	0.39
Water Absorption, g	Loss 0.18 Gain 0.35	0.22+
Crack Bridging @ -25°C		No delamination No loss adhesion No cracking

Heat Stability @ 200°C Penetration, 0.1 mm	Max. 110 @ 25°C Max. 200 @ 50°C	80 155
Low Temp Flex @ -25°C		No delamination No loss adhesion No cracking
Viscosity, s @ 200°C	Min. 2 Max. 15	5

2. Uncured Neoprene Flashing Sheet: **ram Flash 327 HDR Sheet**, shall comply with the following minimum specifications:

<u>TEST</u>	<u>METHOD</u>	<u>TYPICAL TEST RESULTS</u>
Thickness Tolerance, %	ASTM D-412	±10
Specific Gravity	ASTM D-297	1.48 ±.05
Tensile Strength min, psi (Mpa)	ASTM D-412	1500 (10.3)
Elongation, Ultimate min, %	ASTM D-412	250
Hardness, Curometer, A Tear resistance min,	ASTM D-2240	60 ±10
1 bf/in (kN/m)	ASTM D-624 (Die C)	120 (21.0)
Brittleness Temperature, max, F(deg C)	ASTM D-746	-30 (-34)

Flame Resistance	ASTM C-542	Must not propagate flame
Resistance to Heat Aging Properties after 70 h at 212°F Hardness increase max.	ASTM D-573	+ 10
Resistance to Oil Aging Change in Volume, max after 70 h Immersion in ASTM Oil #3 at 212°F	ASTM D-471	+ 80%
Ozone Resistance Condition after Exposure to 100 pphm Ozone in Air for 100 h at 104 F (sample under 20% strain)	ASTM D-1149	No cracks
Resistance to Water Change in Mass, max, after 7 days Immersion at 158°F	ASTM D-471	+ 10%
Water Vapor Permeance (perms)	ASTM E-96	.07

3. Ply Sheet: Poly-Felt 125 VP spunbonded polyester fabric, non-needlepunched, heat set with resin binder, shall comply with the following minimum specifications:

<u>TEST</u>	<u>METHOD</u>	<u>TYPICAL TEST RESULTS</u>
Basis Weight	ASTM D-3776	60 GR/M ²
Grab Tensile/lb	ASTM D-4830	34/lb. MD 32/lb. CD
Elongation/%	ASTM D-4830	37 MD, 42 CD
Trapezoid Tear/lb.	ASTM D-4830	14 MD 12 CD

- | | | |
|----------------|----------------|---------------|
| Ames Thickness | ASTM D-1777-64 | 9.5 mils |
| Fatigue Life | ASTM D-8B | 10,000 cycles |
4. Protection Course: **ram 203**, shall comply with the following minimum specifications:

<u>TEST</u>	<u>METHOD</u>	<u>TYPICAL TEST RESULTS</u>
Weight	ASTM D-461	Min 50 lbs/ 100 sq ft
Asphalt Softening Point	ASTM D-36	220°F - 250°F
Asphalt Penetration	ASTM D-5	15 - 20 dmm
Surfacing & Surface Stabilizer Max.	ASTM D-4601-86	65%

B. Related Materials:

1. Primer: **ram Primer/Surface Conditioner**, shall comply with ASTM D-41 requirements.
2. Pipe, Stack and all Corner Base Flashings: **ram Pipe Boot** and premolded corner pieces, supplied by primary materials Manufacturer and installed in accordance with published flashing details. Neoprene sheet is not acceptable in corners or at pipe and stack flashings.
3. Nails and Mechanical Fasteners: As specified by the fastener Manufacturer for specific application and approved by membrane Manufacturer.

PART 3 - EXECUTION

3.01 PREPARATION

- A. Remove trash, debris, grease, oil, water, moisture and other contaminants from the deck which may affect bond of bitumen to deck surface.

Optional:

Sand-blasting and/or shot-blasting procedures may be required on certain renovation work to provide the best possible surface. If required, provide unit price per square foot in bid documents.

- B. Condition of Surface: Any new concrete surfaces shall be wood float finish ACI301-11.7.3 or better. All concrete shall have cured for a minimum of 28 days or, alternatively, pass the NRCA deck dryness test. All surfaces shall be dry, clean, firm and free from laitance, frost, dust, dirt, oil, unapproved curing compounds or other foreign matter detrimental to performance of the waterproofing membrane. The General Contractor shall certify no wax base curing compounds have been used.

Before commencing work, examine all areas and report in writing to Architect any conditions that will adversely affect successful installation. Do not begin work until the conditions have been corrected. Voids, cracks, holes and other damaged surfaces shall be repaired with materials compatible with **ram-Tough** 250. On existing concrete decks, all old existing membrane and flashings shall be completely removed to bare concrete.

- C. Expansion Joints: Expansion joints shall be sharply formed and free of broken edges or loose aggregate and completely free of preformed joint fillers, sealants or back-up materials to a depth that is at least twice the width of the joint. Curb expansion joints at each side of the joint, either by integrally forming with the slab or securely fastening sulfate treated wood strips to deck. Chamfered edges are required.
- D. Verify concrete surfaces are properly cured, dry and reasonably smooth. Prepare other surfaces according to respective Manufacturer's published instructions. Use cleaning materials and methods necessary to render an acceptable dust free surface, including oil free filtered compressed air or high speed power blowers. Protect adjacent areas from damage with tarpaulin or other durable materials.
- E. No protection from the weather is necessary for **ram-Tough** 250, but temporary protection to installed membrane is required to prevent damage by mechanical gouging, scraping, spilling of oil & solvents or excessive heat.
- F. Delivery and Storage: Deliver and store materials undamaged in original containers with Manufacturer's labels and seals intact.

3.02 INSTALLATION

- A. Surface Conditioner: Each day, prior to application of **ram-Tough 250**, apply surface conditioner, as a fine spray, at a rate of approximately 1 gallon per 300-600 square feet. Allow to dry completely tack free. Do not allow primed surface to be contaminated with construction debris or dust barrier. Re-prime and allow to dry as may be required by job conditions.
- B. Application: Units of **ram-Tough 250** shall be melted in an approved double-jacket oil bath melter under continuous agitation until the material can be drawn free-flowing and lump-free at a temperature of approximately 350°F - 400°F. The **ram-Tough 250** shall be applied at a rate to provide a continuous coating not less than 90 mils thick. Carry slab applications up all vertical wall surfaces a minimum of 8 inches.
- C. Hot fluid applied **ram-Tough 250** shall be applied in a width exceeding the reinforcement fabric roll width. While **ram-Tough 250** is hot and tacky, install specified Poly-Felt 125 VP reinforcement, brooming in place from the side of the fabric. Side laps shall be a minimum of 2 inches with lap placement so that water flows over them and not against them. All laps shall be sealed with hot **ram-Tough 250** under lap. In no place shall reinforcement touch reinforcement. End laps shall be 7 inches. Carry reinforcement up all vertical wall surfaces a minimum of 6 inches.
- D. After reinforcement fabric has been placed and broomed in, install second layer of **ram-Tough 250**, a minimum of 125 mils thick, at all points of the deck and walls. Carry slab applications up vertical wall surfaces a minimum of 8 inches. Do not leave any reinforcement fabric uncoated at end of day's work or in inclement weather. Complete installation of all plies each day including cap sheet.

3.03 FLASHING

Carry hot applied **ram-Tough 250** and reinforcement up all junctions of horizontal deck and vertical surfaces, all changes of plane and all cold joints and cracks as indicated on the drawings. At all parapets, walls, curbs, penetrations, drains, edges, etc., install **ram Flash 327 HDR 60 mil neoprene flashing** with hot fluid **ram-Tough 250** over the reinforcement sheet as shown on the drawings, extending to top of the flashing. Where applicable, mechanically fasten with 1/8 inch flat bar stock termination bar and fasteners approved for the substrate receiver. Overcoat the neoprene flashing with another 125 mil coat of the **ram-Tough 250**.

Application width of neoprene flashing sheet shall be a minimum 6 inches total, minimum 3 inches in any single direction, or under if required by field conditions.

3.04 CRACK TREATMENT

At all cracks and construction joints, apply **ram-Tough 250**, 125 mils thick, then center a 6 inch wide strip of **ram Flash 327 HDR** neoprene flashing over the joint or crack and embed into the warm **ram-Tough 250**. Avoid air pockets. Allow assembly to cool. Reinforcement and flashing should be installed before the continuous, unbroken thick film of bitumen or reinforcement felt is applied over the entire roof surface and flashing areas in accordance with specification in Section 3.02.

3.05 EXPANSION JOINTS

Over expansion joints, up to 2 inches in width with a designed total movement of 50% or less, **ram Flash 327 HDR** neoprene flashing shall be placed over the joint as shown on the drawings and embedded into a 125 mil thick coating of **ram-Tough 250**. The sheet shall be looped into the joint 1-1/2 times the joint width at maximum opening and extend 8 inches onto the deck on each side of the joint. The sheet shall be covered and the loop filled solid and flush with **ram-Tough 250**. Install 1-1/2 inch foam rod and second sheet of neoprene flashing looped over the foam rod. Extend sheet 12 inches onto the deck on each side of the joint. Overcoat flange on each side.

3.06 WATER TEST

Each flat deck contiguous area shall be water tested with 2 inches of standing water for a 24-hour period. Provisions for overflow in event of rain shall be provided. Any area not passing Water Test shall be repaired and retested until watertight. Water Test shall be witnessed and approved by Architect and Manufacturer providing the system warranty.

3.07 PROTECTION COURSE

After Water Test is completed, using **ram-Tough 250** as adhesive and starting at the low points, apply **ram 203 SBS** protection course lapping the side laps a minimum of 2 inches in each direction of drainage gradient.

3.08 FIELD QUALITY CONTROL

- A. Adhesion Tests and Thickness Tests shall be monitored by the Applicator every hour throughout the application process.
- B. Test Cuts shall be made at locations of Architect's or Manufacturer's request:
 - 1. Remove one 12 inch x 12 inch unsurfaced cut per 100 squares of deck area.
 - 2. Follow field audit criteria outlined by ASTM Standards.

3. Send roof cuts to: Structural Research, Inc., Madison, Wisconsin, or Manufacturer approved accredited laboratory for laboratory examinations. Applicator shall allow \$500.00 for testing fees per 100 squares of roof area. Laboratory results shall be submitted by the laboratory directly to the Architect.
 4. Repair sampled areas by filling in the cut-out area then use a "feathered in" patch consisting of Poly•Felt 125 VP and **ram-Tough** 250 following the Manufacturer's and NRCA procedures.
- C. Correct any deficiencies in the deck membrane, if any, (determined by deck cut analysis) as prescribed by material Manufacturer and approved by the Architect.

3.09 CLEANING

- A. Remove equipment, trash, debris and any excess material from the jobsite.
- B. Repair damage and remove any stains caused by work of this Section.

3.10 PROTECTION

General Contractor shall protect finished deck areas from damage during subsequent construction.

<p>MAINTENANCE:</p>

<p>Semi-annual inspections and a systematic maintenance program are recommended to the Owner and Architect. Consult your Barrett Representative or Barrett Approved Applicator for further information.</p>
